

My summer activities in DUNE and ProtoDUNE-SP


A. Cervera

IFIC-Valencia

ProtoDUNE-SP

- Cryostat almost full (7.15 m of LAr which corresponds to 715 tons)
- LAr already covering ground planes and HV rump up can start

<https://np04-slow-control.web.cern.ch/np04-slow-control/app/#!/tinternal>



Detector activation plan

<https://indico.fnal.gov/event/18223/contribution/4/material/slides/0.pdf>

1 *Before end of filling*

- Routine CE noise runs and PD test runs
- Routine Purity Monitor measurement
- After ground planes are covered with LAr, turn off the MPOD channel supplying the voltage to the cathode. Plug in the Heinzinger HV cable, and ramp the voltage to ~10 kV to test the control and monitoring on the system. Voltages up to 20 kV may be considered
 - CE noise run after voltage is set. Monitor current draw during and after voltage ramp
 - Should happen next Monday

2 *Filling completed, before recirculation starts*

Next Monday/Tuesday

- Check the LAr surface with camera, to see whether is flat or shows turbulences/bubbles
 - PD and FEMBs must be off
- Turn on FEMBs and check LAr surface with camera to see whether there are any difference with respect to the previous step
 - PD must be off
- Evaluate a new filter regeneration

3 *After start of recirculation*

Next Monday/Tuesday

- Check the LAr surface with camera, to see whether there are any difference with respect to the previous step
 - PD and FEMBs must be off
- Turn on FEMBs and check LAr surface with camera to see whether there are any difference with respect to the previous step
 - PD must be off
- Cameras, PD, CE turned on. LED and infrared lights turned off.
- Start HV ramping. First set wireplane bias and FC termination voltage to the value correspondent to the targeted Cathode voltage. Then ramp Cathode voltage to the target value
- During HV ramp, monitor CE current draw. At the end of the ramp, take CE noise run

4 *HV ramp: Day 1st*

- Ramp rate: 60 V/s. Target voltage: 50 kV. Wait 30 minutes
- Ramp rate: 30 V/s. Target voltage: 90 kV. Wait 30 minutes
- Ramp rate: 30 V/s. Target voltage: 120 kV. Wait all night
- Take runs... should start to see something close to the wires now..

5 *HV ramp: Day 2st*


- Ramp rate: 30 V/s. Target voltage: 140 kV. Wait 4 hours
- Ramp rate: 30 V/s. Target voltage: 160 kV. Wait 4 hours
- Take runs... should see more now

6 *HV ramp: Day 3st*

- Ramp rate: 30 V/s. Target voltage: 170 kV. Wait 4 hours
- Ramp rate: 30 V/s. Target voltage: 180 kV. Wait forever
- Should be Thursday now. Time for our meeting
- Take runs and see how purity improves!

Next steps

- Today HV=-20 kV successfully
- Going to -180 Kv will take the rest of the week
- After HV ramp up recirculation will start
- The current lifetime is about 0.05 ms and it should go above 1 ms
- This will take between 2 and 3 complete cycles (a complete recirculation cycle takes 5.5 days)
- So we can start taking physics data by the end of the month



My activities

- Look at the DCS panels in general and make sure that everything works as expected. Solve few problems with Xavier and company
- I've been looking on temperature data with Migue
 - trying to understand how to retrieve the data from the DCS
 - temperature maps
 - vertical alignment between Hawaii and Valencia sensors
 - etc
- Install LArSoft and run it, with the help of Pablo
 - Play with it, build my own module, etc
- Manage to compile HighLAND with a new reader for the latest version of LArSoft files.
 - It took a while since I even had to install root 6

DUNE

- TDR must be ready by April
- During August we have been working on the WBS and cost estimates for the CISC consortium

TDR Schedule (Preliminary thoughts)

- September 1 - editors appointed
- October 1 - outlines due
- November 1 – first drafts due
- December 1 – second drafts due
- February 1 – input from independent reviews of second drafts
- March 1 – final drafts due
- April 1 – independent reviews of second drafts complete
- April 15 – submit final drafts to LBNC

Other Deliverables Required for TDRs

- Finalized Cost Workbook
- Final assignments of institutional responsibilities for detector deliverables (funding matrices)
- Finalized construction and installation schedule
- Complete set of interface documents

Cost for our devices

Static T-Gradient Thermometers (SP Module)							
Item	Cost/unit	Quantity	Total	Details/Comment			
Material	14.390,00	6	86.340,00	6 T-gradient monitors, 3 in each side of the cryostat			
Packing & Shipping	2.000,00	1	2.000,00	This covers the crating costs and the costs for shipping to FNAL for testing and then SURF for installation			
Total M&S			88.340,00				
Travel	2.000,00	15	30.000,00	Travel needs to cover both the costs of development and testing, as well as the installation and commissioning work, 52,000 is estimated per trip of one week			
Person-power				See the detailed "Person-power" table below			
Cost Breakdown							
Item	Unit price (€)	Unit	Quantity	Cost	Details/Comment		
Cable	10,00	m	500	5.000,00	48 sensors assuming an average of 10 m per sensor		
Sensors	100,00	unit	55	5.500,00	48 sensors + 10% as backup		
Connectors for sensors	10,00	unit	55	550,00	two IDC-4 connectors (male and female) for each sensor		
Support structure	1.000,00	unit	1	1.000,00	Stainless steel string and associated anchoring system		
Flanges	585,00	unit	4	2.340,00	4 CF63 flanges with 2 SUBD-25 connectors each		
one unit (total)				14.390,00			
Person-power							
Category	# of FTE (1 FTE = 1768 hours/year at FNAL)	How long? (years)	Total hours	Cost/year	Total cost	Basis of Estimate	What Tasks?
Scientist	1	2	3536	0,00	0,00	University funded hence \$0	Design, construction, calibration, assembly, installation and commissioning
Postdocs	0,5	2	1768	40.000,00	40.000,00	Estimate based on postdoc cost at IFIC, Valencia	Design, construction, calibration, assembly, installation and commissioning
Graduate Students	0,5	3	2652	20.000,00	30.000,00	Estimate based on postdoc cost at IFIC, Valencia	Construction, assembly, installation and commissioning
Engineers	0,25	1	442	30.000,00	7.500,00	Estimate based on engineer cost at IFIC, Valencia	Design, assembly and installation
Technicians	0,5	1	884	20.000,00	10.000,00	Estimate based on technician cost at IFIC, Valencia	Construction, assembly and installation
Total			9282		87.500,00		

Individual Temperature Sensors (SP Module)							
Item	Cost/unit	Quantity	Total	Details/Comment			
Material	388,56	100	38.855,50	Assume 130 sensors, 65 above top GPs and 65 below bottom GPs, which corresponds to 1 sensor every 5 m			
Packing & Shipping	2.000,00	1	2.000,00	This covers the crating costs and the costs for shipping to FNAL for testing and then SURF for installation			
Total M&S			40.855,50				
Travel	2.000,00	15	30.000,00	Travel needs to cover both the costs of development and testing, as well as the installation and commissioning work, 52,000 is estimated per trip of one week			
Person-power				See the detailed "Person-power" table below			
Cost Breakdown							
Item	Unit price (\$)	Unit	Quantity	Cost	Details/Comment		
Cable	10,00	m	20	200,00	assuming an average of 20 m per sensor		
Sensors	100,00	each	1,1	110,00	cost of sensor assuming a 10% of sensors as backup		
Connectors for sensors	10,00	each	1	10,00	two IDC-4 connectors (male and female) for each sensor		
Support structure	20,00	each	1	20,00	Teflon and FR4 pieces + 55 bolts and nuts		
Flanges	585,00	each	0,083	48,56	1 CF63 flange with 2 SUBD-25 connectors each for 12 sensors; this is the no. of flanges per sensor, above we multiply this by no. of sensors.		
Total				388,56			
Person-power							
Category	# of FTE (1 FTE = 1768 hours/year at FNAL)	How long? (years)	Total Hours	Cost/year	Total cost	Basis of cost estimate	What Tasks?
Scientist	1	2	3536	0,00	0,00	University funded hence \$0	Design, construction, calibration, assembly, installation and commissioning
Postdocs	0,5	2	1768	40.000,00	40.000,00	Estimate based on postdoc cost at IFIC, Valencia	Design, construction, calibration, assembly, installation and commissioning
Graduate Students	0,5	3	2652	20.000,00	30.000,00	Estimate based on postdoc cost at IFIC, Valencia	Construction, assembly, installation and commissioning
Engineers	0,25	1	442	30.000,00	7.500,00	Estimate based on engineer cost at IFIC, Valencia	Design, assembly and installation
Technicians	0,5	1	884	20.000,00	10.000,00	Estimate based on technician cost at IFIC, Valencia	Construction, assembly and installation
Total			9282		87.500,00		